

## 9. SUMMARY OF ENVIRONMENTAL IMPACTS

## 9.1 INTRODUCTION

9.1.1 Table 9.1 summarises the impacts that have previously been identified, the key mitigation / control measures and the significance of the resulting (residual) impacts. This Table builds on and expands Table 4.1 – Potential Environmental Impacts. An equivalent Table summarising the social impacts of the Project can be found in Appendix G.

Table 9.1 – Summary of Impact Significance Assessment

Ref No	Activity / Source	Aspect	Potential Impacta,b,c	Mitigation / Control Measures	Residual Impact Significance	Comments
Typic	al Operation (ma	in activities)				
1		SO <sub>2</sub> , NOx, HF, PM <sub>10</sub> , PAH		Through design (e.g. LNBs for power plant and furnaces, selection of pre-bake, open furnace technology for anode production, efficient off-gas collection systems, waste heat recovery for gas turbines etc.).  Use of gas treatment systems (e.g. RTO	NOx, PAH, HF: Negligible SO <sub>2</sub> : Negligible (at residential receptors) to Minor (in the vicinity of the	PM <sub>10</sub> emissions are only considered to have a " <b>Moderate</b> " significance on the basis of the existing high background concentrations; the contribution from the Qatalum Project alone is assessed as <b>Negligible</b> .
				for Paste Plant, dry scrubber systems for Bake Plant and Al Plant, seawater scrubber for Al Plant, baghouse for dust	fenceline) PM <sub>10</sub> : <b>Moderate</b>	assessed as Negligible.
	Operation of Qatalum Project main plant	HF, SO <sub>2</sub>	generating operations, oil scrubber for pitch storage etc.)  Use of gas as fuel (rather than oil).  Good operational and process optimisation controls, regular maintenance and testing.	HF: Minor	The assessment indicated that any impacts would be most likely to occur to landscape planting within the MIC Industrial Area and that this would be highly localised to the roadside planting immediately adjacent to the site's south western boundary.  Visual monitoring of plant species in the	
		HF, 5U <sub>2</sub>	impacts on terrestrial habitat & flora.	will be put in place (see Table 8.1).  Development and implementation of site	SO <sub>2</sub> : Negligible to Minor	vicinity of the site will be undertaken on a regular basis.
				specific EMS. See Table 8.1 and Sections 3.11 / 3.12 / 3.15 for full details.		In the unexpected event that damage is observed or suspected, the monitoring programme may be elaborated and further mitigation, such as replanting with more hardy / tolerant species will be considered.



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
		CO, SO <sub>2</sub> , NO <sub>2</sub>	Contribution to ground level ozone formation		Moderate	The SCENR standards for ozone are already exceeded within MIC; thus any impact arising from the potential increase in ozone concentrations has been rated as having a <b>Moderate</b> significance. However, the Qatalum project has minimised emissions with the potential to result in ground level ozone creation so far as it possible.
	Operation of	CO <sub>2</sub> , PFCs	Contribution to global warming		Minor	-
	Qatalum Project main plant	m		Concentration of emissions in work areas will be kept as low as reasonably possible (ALARP).	Minor	
				Design and organisational measures to ensure that occupational exposure will not exceed OELs.		
				Buildings will be properly ventilated, with clean air and, where necessary, fitted with extraction systems.		
				Protective equipment will be made available to personnel in the event of plant malfunction / accidents.		



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
				Through design (i.e. technology / plant selection).		There are no residential receptors in the vicinity of the site.
				Regular maintenance and testing.		No significant species or numbers of mammals, reptiles or invertebrates were
	Operation of		Disturbance to surrounding	A monitoring programme will developed.  Development and implementation of site	Human Health:	observed at or around, the site; although
2	the Qatalum	Noise generation	environment (residential populations, workers and	specific EMS.	Minor Fauna: Negligible	birds use the reedbed area and part of the lagoon near the Original Port Area.
	Project	S .	fauna)	Design and organisational measures will ensure that occupational exposure limits will not be exceeded.		The noise assessment determined that operation of the facilities will not breech the SCENR standards, thus the impact on off-site
				Hearing protection zones will be designated as required.		workers in the MIC Industrial Area should be minimal.
					_	There are no significant receptors within 500 m of the QASCO channel discharge point.
				Through design.	Temperature: Minor	Thermal plume modelling has indicated that the SCENR criteria will not be breached;
		Seawater discharge (heat		Good operational and management practices.	COD/DO: Negligible	even during the winter months when the
3	Aluminium	load, COD, pH,	Degradation in seawater quality	Development and implementation of site		Qatalum discharge ΔT is at its highest.
	Plant	residual chlorine)	quality	specific EMS.	pH: <b>negligible</b>	An aeration system wil be installed to further reduce COD levels and to increase DO levels
	operation – seawater	Cilionine)		A monitoring / control programme will be developed and implemented.	residual chlorine:	in accordance with the SCENR standard.
	scrubber			developed and implemented.	negligible	Residual chlorine will be destroyed by the sulphites formed during the seawater scrubbing process.
4		Seawater discharge (sulphite)	Improvement in quality of QASCO discharge (residual chloride destruction)	Not applicable	Beneficial	The sulphite formed during the seawater scrubbing process will react with, and destroy, the residual chlorine in the QASCO discharge prior to its release to sea



Ref No	Activity / Source	Aspect	Potential Impacta,b,c	Mitigation / Control Measures	Residual Impact Significance	Comments
				No direct discharge, all fresh process water to be re-used for irrigation.		
	Aluminium Plant – fresh	Untreated	Contamination of soil and	Treatment of water to irrigation standards		
5	process water systems	process water	groundwater	Monitoring to ensure irrigation standards are met prior to use.	Negligible	-
				Development and implementation of site specific EMS.		
6	Cooling tower system	Salt aerosol	Increased corrosion potential	Efficient mist eliminators	Negligible	-
	Generation, handling and		leakage from inappropriate Contamination of soil and groundwater	All storage areas holding materials with the potential to contaminate soil / groundwater will be constructed in accordance with international / Qatari standards, on impervious surfaces, including bunds, as necessary.	Negligible	
	storage of process	Spillage /		Emergency response / spill clean up protocols will be in place.		
7	specific wastes hazardous wastes (e.g. spent pot liner)	leakage from inappropriate storage		Wastes will be stored, handled and monitored in accordance with Qatari legislation / regulations.		-
			nt pot	A Project specific EMS, based on the principles of ISO14001, will be developed and implemented; this will include a waste management plan.		
					Groundwater will be monitored on site on a regular basis.	



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments			
Abno	onormal / Upset Operational Conditions								
8	Initial start-up of pots	CO <sub>2</sub> , CO, SO <sub>2</sub> , NOx, HF, PM <sub>10</sub> , PAH, traces of PFC)	Degradation in air quality Contribution to global warming and ground level ozone formation	In general, as for impact No. 1 above.  Additionally, opening of the pots during start up will be minimised, so far as possible and increased suction from the pot-gas collection system will be applied to prevent pot off-gases escaping into the potrooms during the first 2 days.	Minor	This is a "one-off" infrequent event of limited duration and magnitude. During the initial start up only four pots will be started each day, thus only eight pots will be in preheating mode on a daily basis until all pots have been started.			
9	Venting (power station start-up / shut down)	Natural gas	Contribution to global warming	None proposed	Negligible	This is a "one-off" infrequent event of limited duration and magnitude.			
10	Emergency diesel generator / black start generators	CO <sub>2</sub> , CO, SO <sub>2</sub> , NOx, PM <sub>10</sub> , VOC	Degradation in air quality Contribution to global warming and ground level ozone formation	The generators will be of a modern design to minimise emissions.  Regular maintenance and testing will be undertaken to ensure good performance.	Negligible	Use of the generators will be an infrequent event of limited duration and magnitude.			
11	Failure of supply of QASCO discharge	Acidic seawater discharge	Degradation in seawater quality	Discussions will be undertaken with QASCO and a communication system will be established regarding the discharge channel. Safeguards to further prevent / minimise any impact associated with this activity will be incorporated into the Qatalum EMS.	Minor	The discharge will be rapidly neutralised by the natural alkalinity of the seawater before it can reach any receptors that may be affected by an acidic environment.			



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
Gene	ral Activities (Op	erational / Constru	uction / Commissioning)			
						None of the habitats or areas within the proposed Qatalum Site, or in the vicinity of the site, has legal status as a protected area, nor are they nominated for inclusion as Biosphere Reserves under UNESCO's programme.
12	Presence of facilities (construction workers camp,	Footprint (land- take)	Loss of terrestrial habitat / species	It is not possible to directly mitigate against this aspect.	Minor	The artificially created reedbed appears to be drying out; nevertheless it is valuable as a habitat in its own right (providing habitat diversity within an area largely devoid of other vegetation.
	Aluminium Plant, Power Plant, Service Corridor, Port					Compensation is recommended for the loss of the reedbed that is attributable to the Qatalum Project.
13	facilities, storage area for dredged fines)	Visibility	Visual impact	Due consideration will be given to the colour of painted surfaces / buildings.  Some areas of landscaping will be created at the site	Negligible	The Project site is located in a well established industrial area, the landscape of which is already dominated by industrial plant, stacks, flares and night time lighting systems. The scale of the development is small in the context of the overall MIC Industrial Area. There are no nearby residential receptors whose view would be impaired.
14	]	Lighting	Visual impact (night time)	None proposed	Negligible	See Ref. No. 13 above.



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
15	Presence of	Footprint	Footprint	It is not possible to directly mitigate against this aspect.  Altern	Original Port: <b>Minor</b>	
13	Port facilities	(seabed)	Loss of marine habitat		Alternative Port: Negligible	
				Construction and process "wastes" will be re-used / recycled as far as possible.		
	Construction of facilities and operation		2 op. o	Power will be generated from an efficient gas-fired CCGT with heat recovery	Minor	The use of natural resources (raw materials, fuels and water) is inevitable for a manufacturing process and for construction; however, the Project has been designed to minimise raw material use and wastage during construction and operation and to optimise process efficiency.
				Potable water use has been minimised through the selection of seawater cooling systems.		
16				Operational potable wastewater streams will be reused within the process, or used to irrigate landscaping.		
	of plant			Seawater use has been optimised and the majority will be returned to sea.		
				The EMS for operation of the installation will identify opportunities to further minimise the use of natural resources.		
				The Contractor(s) EMP is expected to include plans for minimising the use of natural resources / raw materials.		



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
				During operation, baghouses will be used to collect dust emissions from dust generating activities.		
17	Materials use, storage and	Dust generation and	Smothering of flora and	For operation, a Project specific EMS, based on the principles of ISO14001, will be developed and implemented.	Negligible	There are no sensitive receptors in the
	handling	deposition	fauna	For construction, Contractor(s) will develop and implement an EMP.		vicinity of dust generating activities.
				Dust control measures, such as damping down and covering stockpiles of dusty materials will be considered in the Contractor(s) EMP		
18		Dust generation	Degradation in air quality	As per 17 above.	Negligible to Minor	As per 17 above
				All materials to be stored and handled in accordance with international / Qatari standards / regulations.		
19		Spillage / leakage from inappropriate	sakage from sappropriate torage / Soil and groundwater contamination	For operation, a Project specific EMS, based on the principles of ISO14001, will be developed and implemented.	Negligible	-
		handling		For construction, Contractor(s) will develop and implement an EMP.		
				Emergency response / spill clean up protocols will be in place.		
20			Contamination of seawater and sediment	As per Ref No 19 above.	Negligible	-



Ref No	Activity / Source	Aspect	Potential Impacta,b,c	Mitigation / Control Measures	Residual Impact Significance	Comments
21			Physical disturbance of the seabed, loss of habitat, damage to marine flora and fauna	As per Ref No 19 above.	Negligible	-
22	Maintenance and use of plant,	Dust generation and	Smothering of flora and	For operation, a Project specific EMS, based on the principles of ISO14001, will be developed and implemented.	Negligible	There are no sensitive receptors in the proximity of dust generating activities.
	equipment and transport	deposition	fauna	For construction, Contractor(s) will develop and implement an EMP.		
				As per Ref. No. 17 above.		
23		Combustion gases (vehicle	Degradation in air quality Contribution to global	Equipment, plant and vehicles will be of a recent design and will be regularly maintained and tested.	Negligible to	
23		exhaust) and dust	warming and ground level ozone formation	All vehicles / equipment will be operated in accordance with the manufacturers instructions.	Minor	-
				Speed limits will be observed.		



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
				For operation, a Project specific EMS, based on the principles of ISO14001, will be developed and implemented.		There are no residential receptors in the
				Hearing protection zones will be designated as required.		vicinity of the site.  No significant species or numbers of
			Disturbance to surrounding  For construction, Contractor(s) will develop and implement an EMP.  Humans:		mammals, reptiles or invertebrates were observed at or around, the site; although	
24		Noise environment (residential populations, workers and terrestrial fauna) Equipment, plant and vehicles will be of a populations, workers and terrestrial fauna) Equipment, plant and vehicles will be of a recent design and will be regularly maintained and tested.	<b>Negligible</b> to <b>Minor</b> Fauna:	birds use the reedbed area and part of the lagoon near the Original Port Area.  The noise assessment determined that		
				·	Negligible	operation and construction of the facilities will not breech the SCENR standards, thus there
					in accordance with the manufacturers	
			Speed limits will be observed.			
25		Fuel leaks, particularly	Soil and groundwater contamination	As per Ref No 19 above.	Negligible	-
26		when refuelling / servicing	Degradation in marine water and sediment quality	As per Ref No 19 above.	Negligible	No refuelling of ships will take place at the Qatalum Berth(s).



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
27	Transport (material delivery, workers etc)	Increased traffic (use of roadways and shipping lanes)	Traffic disruption	Centralised control of ships in and out of MIC.  A road Traffic Management Plan will be prepared as part of the construction EMP and the Project EMS.  The construction TMP will be agreed and coordinated with MIC.	Operation & construction - Shipping: Minor Operation - Roads: Negligible Construction - Roads (Original Port): Minor Construction - Roads (Alternative Port): Not assessed	Ships using the Mesaieed Ports will be under the control of the MIC Harbour Master  Qatalum shipping numbers are less than 8% of projected total vessel numbers.  With the exception of the Alternative Port concept scenarios, most raw materials and equipment during construction and operation will arrive by ship and the main issue will be commuter traffic within MIC.  Further evaluation of traffic impacts will need to be addressed for the Alternative Port concept. Further details relating to the Qatalum Port concept will be submitted when selection decisions have been finalised and the engineering works are more advanced.
28	Shipping movements	Ballast water	Degradation in marine water and sediment quality	None proposed.	Negligible	No ballast water will be discharged in the MIC Port Area.
29	Use and storage of hazardous materials / wastes (e.g.	Accidental spillage	Soil and groundwater contamination	As per Ref No 7 above. For construction, Contractor(s) will develop and implement an EMP, which will include a WMP, spill protocols and emergency response plans.	Negligible	-
30	diesel, oils, paints, lubrication fluids)	Spillage / leakage from inappropriate storage	Soil and groundwater contamination	As per Ref No 29 above.	Negligible	-



Ref No	Activity / Source	Aspect	Potential Impacta,b,c	Mitigation / Control Measures	Residual Impact Significance	Comments
31	Production, handling and storage of non-	Spillage / leakage from inappropriate storage	Soil and groundwater contamination	As per Ref No 29 above.	Negligible	-
32	hazardous liquid waste (e.g. domestic / kitchen waste, etc)	Inappropriate storage	Increase of pests / vermin	As per Ref No 29 above.	Negligible	-
				Design of surface drainage system.		Heavy rainstorms are infrequent events in Qatar.
			Soil and groundwater	Retention basin.		
33	Heavy rainfall	Stormwater	contamination	Potentially contaminated rainwater will be collected separately and treated prior to disposal / re-use.	Negligible	
Cons	truction Specific	Activities				
34	Site preparation, filling, grading,	Disturbance to land surface	Loss of / damage to terrestrial habitat, flora and	Contractor(s) will develop and implement an EMP, which will ensure minimal	Minor	None of the habitats or areas within the proposed Qatalum Site, or in the vicinity of the site, has legal status as a protected area.
	levelling and compacting, creation of	and vegetation	fauna	disturbance to off-site areas.		The impact of disturbance would be temporary.
	temporary roadways /	oorary lways /	y s/			Much of the Project area comprises made ground or has been disturbed.
35	access routes etc.	Disturbance to land surface	Disturbance of archaeological remains	None proposed	Negligible	The Community Area Master Plan for MIC established that no sites of archaeological importance exist in the industrial area.



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
36		Dust generation and deposition	Smothering of flora and fauna	Contractor(s) will develop and implement an EMP, which will address dust control.  Dust control measures, such as damping down and covering stockpiles of dusty materials will be considered in the Contractor(s) EMP	Negligible	There are no sensitive receptors in the proximity of dust generating activities.  Any impacts would be temporary.
37		Dust generation	Degradation in air quality	As per 36 above.	Negligible to Minor	There are no sensitive receptors in the proximity of dust generating activities.
38		Noise generation	Disturbance to surrounding environment (residential populations, workers and fauna)	For construction, Contractor(s) will develop and implement an EMP, which will include measures to minimise and control construction noise.  Equipment / plant will be of a recent design and will be regularly maintained and tested.  Occupational exposure limits will not be exceeded.  All equipment / plant will be operated in accordance with the manufacturers instructions.	Humans: Negligible to Minor Fauna: Negligible	As per 24 above.
39	Dredging	Disturbance of the seabed, flora and fauna	Loss of / damage to marine habitat and flora	The dredging Contractor will produce and implement an EMP to reduce and minimise the impacts of dredging.	Original Port: Moderate Alternative Port: Minor	Compensatory measures for loss of the seagrass area due to may be considered if the Original Port concept is pursued.  On the basis that the dredge contractors EMP incorporates and implements all the measures suggested in Section 6.5, the significance residual impact of for both Port concepts and all dredging scenarios would be reduced.
			Loss / damage to fish / fauna	Monitoring will be undertaken as described in Section 6.5.	Minor	



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
40		Disturbance and re- suspension of contaminated sediment	Degradation of water and sediment quality	As per 39 above	Original Port: Negligible Alternative Port: Minor to Major	On the basis that the dredge contractors EMP incorporates and implements all the measures suggested in Section 6.5, as appropriate, the significance residual impact of the Alternative Port concept and all dredging scenarios would be reduced to <b>Minor</b> .
41		Disturbance and re- suspension of sediment	Smothering of marine flora and fauna and increased turbidity	As per 39 above	Original Port: Moderate  Alternative Port: Dredge scenarios 1 & 2: Minor Dredge scenario 3: Minor to Moderate	As per 40 above.
42	Preparation of dredged materials - dewatering	Run-off water containing fine sediment	Smothering of marine flora and fauna and increased turbidity	As per 39 above	Minor	There is only sparse seagrass coverage and low species numbers and diversity in the vicinity of the anticipated water run-off discharge.



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments			
	Preparation, storage and use of dredged materials	Contaminated sediment	Degradation of soil and groundwater	The dredging Contractor will produce and implement an EMP to reduce and minimise the impacts of dredging.	Original Port: Negligible Alternative Port: Minor	The dredge areas for the Original Port concept are uncontaminated; the possible dredge areas for the Alternative Port may contain hotspot areas of localised TPH / metals contamination.			
43				For the Alternative Port concept, a predredge sediment survey will be carried out to identify any contamination hotspots; to be avoided during dredging.					
				Monitoring of dredged material prior to use.					
Comn	Commissioning								
44	In situ testing of gas fired turbines and furnaces	Combustion gases (CO <sub>2</sub> , CO, NOx and water vapour)	Degradation in air quality Contribution to global warming and ground level ozone	Other than ensuring that the amount of testing is kept to the minimum requirement, no specific measures are proposed.	Negligible	Magnitude and duration of emissions is expected to be trivial relative to those from operation.			
45	In situ testing of Power Plant	Natural gas venting	Contribution to global warming and ground level ozone	Other than ensuring that the amount of testing is kept to the minimum requirement, no specific measures are proposed.	Negligible	Magnitude and duration of event is expected to be trivial relative to operation.			
46	In situ testing of main plant	SO <sub>2</sub> , fluorides, PAH, particulates, traces of PFC	Degradation in air quality Contribution to global warming and ground level ozone	Other than ensuring that the amount of testing is kept to the minimum requirement, no specific measures are proposed.	Negligible	Magnitude and duration of emissions is expected to be trivial relative to those from operation.			
47		Noise generation	Disturbance to surrounding environment (residential populations, workers and fauna)	Other than ensuring that the amount of testing is kept to the minimum requirement, no specific measures are proposed.	Humans: Negligible to Minor Fauna: Negligible	Duration of event is expected to be trivial relative to operation.			



Ref No	Activity / Source	Aspect	Potential Impact <sup>a,b,c</sup>	Mitigation / Control Measures	Residual Impact Significance	Comments
		Process water effluent	Soil and groundwater contamination	No untreated effluents will be discharged to the environment.	Negligible	-
48				The Contractor(s) will develop and implement an EMP, which will include plans to minimise and dispose of any aqueous wastes.		
				Where necessary, permits / approvals for the discharge of process effluent from testing activities will be obtained by the Contactor(s).		
49		Seawater discharge	Degradation of seawater quality	As per 48 above.	Negligible	-